



Willow Run Test Track St-Ypsilanti, MI

PROJECT DATE
September 2017

SUBSTRATE
Concrete

INTRODUCTION

The American Center for Mobility is constructing a facility in Ypsilanti, MI to test vehicles, roads, infrastructure and communication systems as it relates to Automated Vehicle Technology Development. The site comes with a number of structures already in place including double overpasses, a railroad crossing and a highway loop. Wasser's Polyflex Bridge Deck Waterproofing System has been installed to protect the bridge assets from the insidious effects of corrosion and decay



OWNER

American Center for
Mobility

PROJECT

Willow Run Test Track
Bridge Deck
Waterproofing

CONTRACTOR

Z Contractors Inc.

SYSTEM

Wasser Polyflex Bridge
Deck System
(Spray applied)

SURFACE PREPARATION

Shot Blast and Hand
Grinding

1st Coat

Wasser Polyflex 111PU
Primer

2nd Coat

Wasser Polyflex 311 Tan

3rd Coat

Wasser Polyflex 411 Black